

Tender Notice(01)

भारत सेवा संस्थान द्वारा संचालित सी0बी0गुप्ता बी0एस0एस0 महाविद्यालय, चन्द्रावल लखनऊ के सामने पड़ी खाली भूमि की बाउण्ड्रीवॉल बनाने हेतु निविदाएं आमंत्रित की जाती है, जिसका विवरण निम्नवत है:

Sl.no	Particulars	Quantity	Unit	Rate
1	Total Lenth of boundary wall is approx.	455	R.MTR.	
2	No Slits to be provided in the rear side boundary side adjacent of school boundary.			
3	Laying Cement concrete 1:4:8 (1 cement, 4 fine sand and 8 brick aggregate of 40 m.m size) in foundations and its ramming till it is properly consolidated by pouring water as required, including cost of material and labour and T&P etc. required for the work.			
4	First class brick work in 1:6 cemet sand mortar (1 cement, and 6 fine and coarse sand) in foundations as shown in the drawing upto plinth level including cost of material and labour and T&P etc. required for the work, including cost of curing by water for required period.			
5	Laying D.P.C over foundation brick work, 3.7 cm($1\frac{1}{2}$ ") thick cement concrete (1 cement, 1.5 coarse sand and 3 graded stone grit) mixed with required water proofing compound as shown in the drawing, including cost of material and labour and T&P required for the work. curing with water shall also be done.			
6	First class brick work in super-structure in 1:4 cement sand mortar (1 cement and 4 coarse sand) including cutting and moulding of bricks as required and also making a slit as shown in the drawing and placement of reinforcement steel bars in position as shown in the drawing including cost of material and labour and T&P etc. as required for the work, including cost of curing by water for 28 days			
7	Supplying and laying mild steel deformed bars of diameter as shown in the drawing including its straightening, over lapping at joints, and bending and binding, including wastage and cost of material and labour and T&P required for the work.			
8	12m.m thick plaster in 1:6 cement and mortar (1 cement and 6 fine and coarse sand) including cost of material and labour and T&P required for the work, including cost of curing by water till drying.			
9	Applying branded wall Putty over newly plastered and dried wall and making it smooth by sand paper and painting two coats of specified exterior weather coat paint of colour as directed at site, the second coat by applied when first coat has dried up, including cost of material and labour and T&P etc. required for proper completion of work.			
10	One entrance gate of M.S of size 5mx1.8m and another entrance gate of m.s of size 2.4x1.8 m to be provided as directed.			

Terms and conditions:

1. A sum of Rs. 20,000/- as earnest money alongwith tender documents deposited through Bank Draft in the name of Bharat Seva Sansthan.
2. All documents including drawings are to be signed by the tenderer failing which the tender shall be rejected without giving any reason.
3. Tenderers can be asked to submit their analysis of rates for justifying their quoted rates.
4. Last date for depositing of tender is 27-01-2021 at 4:00 PM and tender will be opened on same date at 4:30PM
5. Drawing enclosed.

Note : Any other work if not mentioned in the details provided but required for the completion of the building work upto the satisfaction of work incharge like roof terracing, windows, antitermite, Plinth beam, electrical, plumbing etc, should be considered while quoting the rates.

General Secretary
Bharat Seva Sansthan
2-Rana Pratap marg,
Moti Mahal, Lucknow-226001