

निविदा (03)

भारत सेवा संस्थान द्वारा संचालित चन्द्रभानु गुप्त ग्राम विकास योजान एवं जनहितकारी अस्पताल, कोटवा सडक, हथौँधा, बाराबंकी, में रैन वसेरा निर्माण कार्य के लिए निविदा।

Si. No.	Item	Area	Unit	Rate	Amount
1.	Providing and injecting chemical emulsion for preconstructional antitermite treatment and creating a chemical barrier under and alround the column pits wall trenches basement excavation top surface if plinth filling junction of wall and floor, along the external perimeter of binding expansion joints, surrounding of pipes and conduits etc.	30.49			
2.	Providing unit of reinforced cement concrete 1:1.5:3 mix (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm. Nominal size) of strength not less than M-150 in lintels over door, Windows & slab excluding supply of reinforcement & its bending. Including necessary centering & shuttering etc. & also Inc. supply of all materials, labour T&P etc. required for proper completion of the work. with curing complete.	0.12			
3.	As in item 6 but for the lighter beams i.e. having spans upto 6 m. (Using 1:2:4 Mix concrete).	25.87			
4.	As in item 6 above but in R.C.C. columns in 1:2:3 having strength not less than M-150.	40.21			
5.	Class 150 brick work in 1:5 cement and fine sand of 1.25 fineness modulus mortar in foundation and plinth including supply of all materials, labour and tools and plants etc. required for proper completion of the work .	285.32			
6.	Class 150 brick work in 1:5 Cement & fine sand of 1.25 fineness modulus mortar in super structure above plinth level upto floor one level (upto one storeys) including necessary cutting and moulding of brick work as required.	29.87			
7.	Supply & Fixing of flush Doors commercial quality conforming to I.S. 2202 part 1 (1983) including Fixing of wooden cleats & stoppers & including fixing and adjustment of hinges, springs & other fitting but excluding their supply & including painting with two coats of black japan paint on all iron fitteing with necessary screws to be supplied department.	28.13			
8.	Fabrication of Grill/Stair case railing.	3.50			
9.	Mild steel or iron work such as reinforced concrete or reinforce brick work (when not included in over all rates) wrought to required shape as necessary including bending for proper completing of work and including supply of steel its wastage bend hooks and authorised overlapping shall be measured unto floor two level.	30.72			

10.	15 mm. Cement plaster in single coat on rough side single or half brick wall for interior plaster upto floor two level including arrises internal rounded angles not exceeding 80 mm. In grith & finished even and smooth.	490.98			
11.	10 mm. Cement plaster in single coat on fair side single or half brick wall for interior plastering upto floor two level including arrises internal round angles not exceeding 80 mm. In grith & finished even and smooth no extra for mixing any additive.	1066.00			
12	10 mm. Plastering on ceiling & soffit of stairs upto floor two level instead of plastring on walls (1 cement:3 course sand.	530.37			
13.	Supplying & fixing 5 mm. (1/4" thick china white glazed tiled in flooring or in skirting or dado laid with 1:3 cement & approved course sand mortar finished with white cement slurry jointing & polishing comolete including supply of all materials labour & tool plants etc. required for proper completion of work.	266.00			
14.	Painting two coats over priming coat on steel & other metal surfaces upto 10 cm. Width or small articles not exceeding 0.10 Sqmt. in areas with superior synthetic enamel such as luxor-3Hi-gloss aqulite superlac dulex soecified finishing to give an even shade & including cleaning the surface of all dirt dust & other foreion matter sand papering & knotting including cost of all matterials labours tools & plants etc, required for proper completion of work.	140.12			
15.	Same as in item No. 21 above but on new wood surface.	130.12			
16.	Distempering two coats with Oil bound distempering of approved band & of required shade on undercoated wall surface to give an even shade over & including a priming coat with cement primer of approved brand & manufacture such as berger J.&N. shalimar, asian paints after thoroughly finised the surface free from mortar dropping and other foreign material and also including preparing the surface even with plaster of paris of approved synthethic material and sand prepared smooth including cost of all materials .	250.47			
17.	White washing with lime on under coated wall surface 3 coat to give an even shade including thoroughly broming the surface to remove all dirt. Dust mortar droop & other foreign matter.	0.00			
18.	Finishing wall with 1 two coat of water proofing cement paints of approved make such super snowcem, durrocem robiacem, guttucem supercem quality & of required shad on undecorated wall surfaces (two coat) over & including one cost white cement primer to give an even shad after thorughly brushing the surface to powdered materials including curing & cost of all matterials.	500.47			

19.	Electrical work including slab pipe fitting (50 Nos.), fanbox (12 Nos). modular completed board (6 Nos.) & wire (25 box) with Labour charge.	-			
20.	W/S Sanitary fitting & plumbing work including WC (2 Nos.) Tap (8 Nos.) Wash basin (2Nos.) Internal pipe fitting (0.75 inch) (24 Nos.) System (2 Nos.) Chambers/ Mandrop holl (2 Nos.)shall be raised upto road level with all labour and materials complete.	-			

Terms and conditions:

1. A sum of Rs. 20,000/- as earnest money along with tender documents through Bank Draft in the name of Bharat Seva Sansthan.
2. All documents including drawings are to be signed by the tenderer failing which the tender shall be rejected without giving any reason.
3. Tenderers can be asked to submit their analysis of rates justifying their quoted rates.
4. Last date for depositing of tender is 31-01-2021 at 4:00 PM and tender will be opened on same date at 5:00PM.
5. All work is required to be done as per drawings.
6. No advance can be sanctioned to contractors.
7. After completion of work payment will be made on submission of bill through Unit Incharge.
8. 5% security will be retained from final bill, which will be returned without interest on completion of one year. In case any defect found in work, contractor may get repaired otherwise security will be forfeited
9. Drawing Enclosed.

Note : Any other work if not mentioned in the details provided but required for the completion of the building work upto the satisfaction of work Incharge like roof terracing, windows, antitermite, Plinth beam, electrical, plumbing etc, should be considered while quoting the rates

General Secretary
Bharat Seva Sansthan
2- Rana Pratap Marg
Moti Mahal Lucknow

